

Sidewalk Concrete Replacement

- Saw-cut and excavate areas to a depth of 10" and compact sub-base.
- Install 4" of DGA limestone and compact.
- Drill and install dowry pins as needed to existing structures.
- Form and pour 6" of 4000 PSI concrete to be hand and tool finished.
- Apply concrete curing agent.
- Approximately 350 SF area